



The Institution of Engineers (India)

AN ISO 9001 : 2015 CERTIFIED ORGANISATION
(ESTABLISHED 1920, INCORPORATED BY ROYAL CHARTER 1935)
8 Gokhale Road, Kolkata-700 020

A Century of Service to the Nation

SP/T-1802

Date: 28.08.2023
Due Date : 08.09.2023

NOTICE INVITING TENDER

Sub :Quotation for Renovation of Drainage System near Staff Quarter Area and Restructuring of Drainage System on the South Portion of Old Guest House of IEI HQ

Sealed quotation is invited for Renovation of Drainage System near Staff Quarter Area and Restructuring of Drainage System on the South Portion of Old Guest House of The Institution of Engineers (India) at 8 Gokhale Road, Kolkata -700020 as per enclosed BOQ (Annexure-I & II). The tender document is also available in our website www.ieindia.org

The sealed quotation is to be submitted in prescribed format duly stamped and signed and dated as their unconditional acceptance to the terms prescribed by The Institution of Engineers (India).

The sealed envelope duly superscribed, "Quotation for Renovation of Drainage System near Staff Quarter Area and Restructuring of Drainage System on the South Portion of Old Guest House of IEI HQ" should be addressed to Director (Administration), The Institution of Engineers (India), 8 Gokhale Road, Kolkata-700020 and submitted at the Institution's address by hand. The quotation must reach to this office within time and date i.e. upto 4:00 PM of 08.09.2023.

Terms and Conditions:

- 1) IEI reserves the right to accept or reject the quotation in part or full without assigning any reason whatsoever.
- 2) Payment will be made on actual basis after successful completion of the work.
- 3) Standard LD clause @2% per week or part thereof subject to maximum 10% will be charged for delay in completion of the work.
- 4) All disputes shall be subject to Kolkata Jurisdiction only.

Thanking you,

Yours faithfully,

Encl. : As stated


Director (Administration)



Renovation of Drainage System near Staff Quarter Area

Sl.No	Description	Qty.	Unit	Rate	Amount	
					Rs.	P.
1.	a) Taking out of Old Cement Plaster from both side existing drainage wall.	L.S.	L.S.	L.S.		
	b) Laying 125mm thick Cement Brick Wall of existing Drainage Guide Wall.	10.00	m ²			
	c) Cement plaster at both side of drainage wall.	17.50	m ²			
	d) Plain cement concrete over the Brick wall before RCC slab fixing.	25.00	r/mtr			
	e) Net cement punning.	17.50	m ²			
2.	Sand filling	7.25	m ³			
3.	Brick soling over the basement.	25.00	m ²			
4.	Laying plain cement concrete over item no.-3	0.812	m ³			
5.	Charges for Cement Sand Mortar 1:3 in bed level for tiles fitting or, (Paver Block)	25.00	m ²			
6.	Supply and Laying Paver Block over the walk way.	25.00	m ²			
7.	Supply and fixing RCC cover Slab over the drainage wall.	6.50	m ²			
				Total :		
				Add GST :		
				Grand Total :		

(Amount in words _____)

Name of the Company:

Address:

Contact No.:

E-mail:

Signature with date and seal


P. Roy

Reconstructing of Drainage System on the South Portion of Old Guest House

Sl. No.	Description	Quantity	Unit	Rate	Amount	
					Rs.	P.
1.	Earth work excavation and dressing and labeling	L.S.	L.S.			
	<u>Providing Drainage Boundary Wall</u>					
2.	a) Brick soling	3.60	m ²			
3.	b) Plain cement Concrete over the brick soling.	3.60	m ²			
4.	c) Laying 5" brick wall.	3.60	m ²			
5.	Supply RCC 3" cover slab.	2.80	m ²			
6.	Supply and covering polythene sheets under bed level of paver block.	28.80	m ²			
7.	Providing cement sand 6:1 mortar necessary use in lower portion of paver block fixing work.	28.80	m ²			
8.	Supply and fixing paver block in Back Side Compound	28.80	m ²			
9.	Charges for garbage and excess earth removing and filling as necessary.	L.S.	L.S.			
				Total :		
				Add GST :		
				Grand Total :		

(Amount in words _____)

Name of the Company:

Address:

Contact No.:

E-mail:

Signature with date and seal


 P. P. P.